

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .					
Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
PART A: FURNITURE WORK -					
1	<u>Façade on Front Side [Entrance] :</u> Providing & fixing in position aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond / Alukbond exterior grade 4mm thick with composite of [0.5mm - 3mm - 0.5mm] including fabrication for the same with [Dow corning 789] masking tape, necessary scaffolding etc as detailed in drawing complete in all respects.	100.00	sft		
2	<u>False Ceiling [Armstrong] :</u> Providing & fixing in position false ceiling in Armstrong 600x 600mm x 15/16mm dune supreme RH 99 Prima tile with tegular edge framework as specified by Armstrong Co. with suspenders wherever required. including finishing with White Plastic Emulsion Paint etc. complete in all respects.	1400.00	sft		
3	<u>False Ceiling [Gypsum Board] :</u> Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontals & verticals fixed over GI framework as specified by India Gypsum Co ltd including finishing with White Plastic Emulsion Paint etc. complete in all respects.	400.00	sft		
4	<u>Entrance Door :</u> Providing & fixing entrance door [glazed] as per drawing in Silver Anodised aluminium door section [Jindal make] in top and bottom, glazed with 12mm thick glass of approved make with etching and frosting. Item to include floor springs, lock, all necessary hardware of SS finish as approved by the Architect complete in all respects	180.00	sft		
5	<u>Front Office Counter :</u> Providing & fixing in position front office counter 2'6" wide as per drawing . comprising of the following complete in all respects : i] Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edges of the working top shall be provided with 1 1/4" x 1" teak wood moulding finished with melamine polish. Inside edges will be provided with 1/2" x 1" teakwood beading patti	16.00	rft		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	with melamine finish.				
ii]	Vertical facia[Apron] made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
iii]	Vertical drop [horizontal band] shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light, 1mm thick groove shall be provided at the joint of two different shades of laminate.				
iv]	Glazed partition above working top to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed SS finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish				
v]	3'10" high boxing [10"x 10"] made with 18mm thick plywood finished with 1mm thick laminate including providing & fixing 6mm thick square frosted glass at a height 3'2" above finished floor level				
vi]	1'9" high boxing [5"x5"] made with 12mm thick plywood finished with 1mm thick laminate.				
vii]	Vertical supports made with 18mm thick plywood finished with white enamel paint.				
viii]	Telescopic CPU stand/ ready made keyboard tray shall be provided of approved model and make.				
ix]	Footrest made with teakwood member of size 4"x 1 1/2" finished with french polish.				
x]	Drawer units as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm laminate and all other sides shall be finished with white enamel paint The drawers will be provided with handles [Stainless steel finish] and channels as per approval of the project consultant/Bank.				
xi]	Boxing as per drawing made with 12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for electrical conducting and at the bottom for the LAN cabling/ telephone wire				

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	conducting.				
	The item to include all necessary hardware and fittings in Stainless steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"x 10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided. Fixing the glass are to be provided.				
6	Cash Counter :	16.00	rft		
	Providing & fixing in position cash counter 2'9" wide as per drawing No [4-5 and 6] comprising of the following -				
i]	Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edges of the working top shall be provided with 1 1/4" x 1" teak wood moulding finished with melamine polish. Inside edges will be provided with 1/2 x 1" teakwood beading patti with melamine polish.				
ii]	Vertical facia[Apron] made with 18mm thick plywood finished with 1mm thick groove at the joint of laminates of two different shades of laminate.				
iii]	Vertical drop[horizontal band] shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light, 1mm thick groove shall be provided at the joint of two different shades of laminates.				
iv]	Glazed partition of 1'4" height above working top provided with 12mm thick toughened and frosted glass besides non-transparent film from inside fixed to partition as per fixing details and to boxing with concealed SS finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.				
v]	Transaction top shall be provided with 12mm thick tpughened glass [partly glazed partly frosted] fixed horizontally with concealed stainless steel D bracket				

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	Both exposed edges [inside & outside] shall be moulded and finished in mirror polish.				
vi]	Glazed partition having height 1'0" above the transaction top [in facia] shall be provided with 12mm thick glass [clear] with cut out of 8"x 4" as per drawing The edges of cut out and the top edge of glass are to be mirror polished and to be fixed on partition as per fixing details and to boxing with concealed SS finished 'D' brackets as shown in glass[clear] above the slit to be fixed to partition as per fixing details and to boxing with concealed SS finished 'D' brackets as shown in the drawing. The exposed edges shall be finished in mirror polish.				
vii]	7'7" high boxing [10"x 10"] made with 18mm thick plywood as per drawing with 1'6" horizontal extension at the top including providing & fixing 6mm thick square frosted glass at a height of 5"-11" above finished floor level				
viii]	1'9" high boxing [5"x 5"] made with 12mm thick ply finished with 1mm thick laminate are to be provided.				
ix]	Telescopic CPU stand/ ready made keyboard tray shall be provided of approved model and make.				
x]	Footrest made with t.w. member of size 4"x1 1/2" finished with french polish.				
xi]	Drawer units as per drawing shall be provided and each drawer should have vertical partitions for keeping the currency notes and multipurpose Godrej lock. Facia of drawer unit shall be finished with 1mm laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles [Stainless Steel finish] and channels as per approval of the Architect / Bank.				
xii]	Boxing as per drawing made with 12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/ telephone wire conduiting. The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind				

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	the vertical drop and also in the 10"x 10" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing as directed.				
7	Solid Full Height Partition : Providing & fixing solid full height partition in frame work including door in 2'x2' grid [horizontally and vertically] comprising of 2"x 1 1/2" teakwood section with 6mm thick plywood on both sides finished with 1mm thick laminates of approved make and colour as shown in drawing no 17. Item to include 2"x 2" t.w. for door frame. All exposed t.w. surfaces to be finished in melamine polish of matching laminate color as directed including all necessary stainless Steel finish fittings / haedware, door closers, Godrej locks and wood preservative paint etc as per list of approved material and as approved by the Project Concultant/ Bank complete in all respects. [Note - In case of false ceiling, the vertical t.w. member to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only]	180.00	sft		
8	Partly Glazed Full Height Partition : Providing & fixing in position partly glazes full height partition work as shown in the drawing no10 including door as shown in the drawing no 12 in frame work at 2'x2' grid [horizontally & vertically] comprising of 2"x 1 1/2" t.w. section and / or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1mm thick laminate of approved shede and color as shown in the drawing Item to include 8mm thick glass with etching and frosting as per design and 2"x 2" t.w. member for door sides and glass sides and t.w. door frame to take 8mm thick glass with etching and frosting. All exposed t.w. surfaces to be finished in melamine polish of matching laminate color as directed including all necessary stainless Steel finish fittings / hardware door closers, Godrej locks and wood preservative paint etc as per list of approved material and as approved	230.00	sft		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	by the Project Consultant / Bank complete in all respects.				
	[Note - In case of false ceiling, the vertical t.w. member to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only]				
9	Partly Glazed Partition for Cash Cabins : Providing & fixing in position 7'7" high partly glazed partition for cash cabins as per drawing . including door ,in frame work at 2'x2' grid [horizontally & vertically] comprising of 2"x 1 1/2" t.w. section and or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1mm thick laminates of approved shade and color as shown in drawings. Item to include 8mm thick glass with etching and frosting as per design & 2"x 2" t.w. member for door sides and glass sides and t.w. door frame to take 8mm thick glass with etching & frosting. The door will be provided with t.w. louvers finished in melamine polish of matching laminate colour. The doors are also to be provided with Godrej night latch Two wooden trays are also to be provided as per drawings. Necessary cutouts are to provided in the glass and the edges of the glass cutouts are to be finished in mirror polish. All exposed t.w. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/hardware door closere, Godrej locks and wood preservative paint etc as per list of approved material and as approved by the Project consultant / Bank complete in all respects	280.00	sft		
10	Partly Glazed Low Height Partition : Providing & fixing in poition partly glazed low height partition [21/2" thick] in frame work with t.w. vertical members at 2' c/c and 3 horizontals members at equal distance comprising of 2"x 11/2" t.w. section with 6mm plywood on both sides finished with 1mm thick laminate of approved make and shade. . Item to include 12mm thick glass [clear/frosted] to be fixed as shown in drawing	25.00	sft		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	The exposed edges of the glass to be finished in mirror polish. T.w. runner should be melamine polished in matching colour of laminate etc complete in all respects				
11	Manager's Table / Officer's Table : Providing & fixing in position manager's table of size 6'x 2'6" as per drawing no 6/ officers table of size 5'x 2'3" as per drawing no 5 including side storage(3'x1'6') [credenza] by using 25mm thick plywood for top and 18mm thick plywood for all other horizontals and verticals members. Telescopic CPU stand/ ready keyboard tray shall be provided of approved model & make. Footrest made with t.w. member of size 4"x11/2" finished with french polish. Side storage [credenza] as per drawing shall be provided. Facia of side storage shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint. The side storage shall be provided with handles [SS finish] and channels as per approval of the Project Consultant/Bank. All exposed plywood surfaces to be finished with 1mm thick laminate of approved make & shed and all exposed edges of table top & ply verticals to have 1"x 1/4" t.w. lipping. All exposed t.w. sections to be melaminated & internal surfaces to have white enamel paint as directed. Item to include plywood boxing, all necessary hardware and fittings in SS finish, lipping to all edges etc complete in all respects	1.00	each		
12	Staff Table : Same as above(item no.12) with size 4'3" x 2' with side unit i.e.credenza(3'x1'6")	6.00	each		
13	Full Height Storage / Low Height Storage / Back Storage [Credenza] : Providing & fixing in position full height storage / low height storage / back storage [credenza] respectively using plywood of required thickness finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint as detailed therein.				

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
	The storage units shall be provided with handles				
	[SS finish] as per approval of the Project Consultant/Bank.				
	All exposed plywood surfaces to be finished with 1mm thick laminate of approved make & shade and all				
	exposed edges of plywood to have 1"x 1/4" t.w. lipping				
	All exposed t.w. sections to be melaminated in matching colour laminate and internal surfaces to have white				
	enamel paint as directed. Item to include all necessary				
	hardware and fittings in SS finish, Godrej multipurpose locks including magnetic ball catcher etc complete in all respects.				
	_765 mm high	40	sft.		
	_1200mm high	65	sft.		
	_2100 mm high	25	sft.		
14	Providing and fixing of 100mm thick vertical blinds with with necessary accessories like channel ,string, control unit ,fabric etc. complete.	140.00	sft		
15	POP PUNNING : Providing and applying Plaster of Paris punning on average 15mm thickness on ceiling, walls and columns to bring the surface in plumb line and level. Rate will be inclusive of scraping, leveling and preparing the surface as also grooves above skirting, around window and door frames. Rate to include scraping, neeru / any other finish on the existing plastered surface.	1200.00	sft		
16	PAINTING : Providing and applying 2 coats of plastic emulsion paint over 1 coat of primer of approved shade and colour on walls, columns and ceiling. The job is inclusive of scraping, leveling and preparing the surface, applying primer, etc.	1400.00	sft		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .					
Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
17	ENAMEL PAINTING : Providing and applying 2 coats of enamel paint over 1 coat of primer of approved shade as per direction of the Architect. The job is inclusive of scraping, leveling and preparing the surface, applying primer, etc.	250.00	sft		
TOTAL					
PART B ELECTRICAL WORK -					
A] FIXTURES -					
1	Supply & installation of direct indirect recessed mounted luminarie with 2 no of 36w PL tube. [FUSION - Wipro make - WCP 64236 SGW]	5.00	no		
2	Supply & installation of indirect direct recessed mounted luminarie with 2 no of 36w PL tube. [SOFTLITE - Wipro make - WCP 63236 SGW]	22.00	no		
3	Supply & installation of 2x 18w down lighter fittings with PL tubes. [Wipro make - WCP 39218]	6.00	no		
4	Supply & installation of 12v, 50 w Halogen down lighter with 50w lamp & Transformer [ECT 75] [Wipro make - WCQ 22150]	4.00	no		
5	Supply & installation of wall mounted fan [Bajaj / Crompton make] with acrylic blades.	10.00	no		
6	Supply & installation of 9" exhaust fan	2.00	no		
7	Providing & fixing of ceiling fan [1200 mm]	4.00	no		
TOTAL					
B] Electrification for Computerisation					
1	Supply & installation of 25A DP MCB in suitable metal enclosure. [Legrand]	1.00	no		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
2	Supply & installation of reynolle plug socket with appropriate MCB's [Legrand]	6.00	no		
3	Supply & installation of 8 - way DB with three phase incoming and single phase outgoing [VTPN] with Legrand - 607751] : Incoming - 63A TPN MCB Outgoing - 32A DP MCB - 9 Outgoing - 20A SP MCB - 2 Outgoing - 16A SP MCB - 1 Outgoing - 10A SP MCB - 3	1.00	no		
4	Supply & installation of 4 - way DB with three phase incoming and single phase outgoing [VTPN] with Legrand - 607750] : Incoming - 63A TPN MCB Outgoing - 32A SP MCB - 5 Outgoing - 20A SP MCB - 2 Outgoing - 16A SP MCB - 1 Outgoing - 10A SP MCB - 4	1.00	no		
5	Supply & installation of UPS SPN DB 16 - way SPN DB with [Legrand - 607713] : Incomer - 40A DP MCB Outgoing - 10A SP MCB - 13	1.00	no		
6	Supply & installation of UPS SPN DB 12 - way SPN DB with [Legrand - 607712] : Incomer - 40A DP MCB Outgoing - 10A SP MCB - 13	1.00	no		
7	Supplying wiring & connecting 2 run of 6 sqm PVC copper conductor and 1 run of 2.5 sqm copper conductor through PVC conduit [HMS] with its specials (with DP switches where ever necessary as per Architects/Bank's instructions)	45.00	m		
8	Supplying , wiring & connecting 2 run of 4 sqm PVC copper conductor and 1 run of 2.5 sqm PVC copper conductor through PVC conduit [HMS] with its specials.(with DP switches where ever necessary as per Architects/Bank's instructions)	55.00	m		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .

Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
9	Supplying , wiring & connecting 3 run of 2.5 sqm PVC copper conductor through PVC conduit [HMS] along with its accessories.(with DP switches where ever necessary as per Architects/Bank's instructions)	40.00	m		
10	Supply, fixing, wiring & connecting 2 no of 3 pin 5A modular socket and switch with indicator with 2 runs of 2.5 sqm PVC copper conductor and 1 run of 1.5 sqm PVC copper conductor running through PVC conduit [HMS]with its specials from DB to work station through floor,wall , trunking box in concealed form. Cost should be inclusive of chiseling the floor/wall & finishing with 1:2:4 cement concrete in case of floor & POP in case of wall. Every work station will have separate circuit from main switch to switch board.	12.00	no		
11	Supply, fixing, wiring & connecting 2 no of 3 pin 5A modular socket and switch with indicator with 2 runs of 2.5 sqm PVC copper conductor and 1 run of 1.5 sqm PVC copper conductor running through PVC conduit [HMS]with its specials from DB to work station through floor,wall , trunking box in concealed form. Cost should be inclusive of chiseling the floor/wall & finishing with 1:2:4 cement concrete in case of floor & POP in case of wall. Every work station will have separate circuit from main switch to switch board.	6.00	no		
12	Supply & installation of earthing station 600 x 600 x 3.5mm thick copper earth electrodes as per IS standards with salt,charcoal,chamber,GI cover, funnel etc.complete.	2.00	no		
13	Supply & installation of 1C x 6 sqm copper insulated 1.1 kv grade unarmored conductor through 20mm metal conduit for earth pit to UPS room	25.00	m		
14	Supply & installation of 8 SWG twin GI conductor for GI earthing.	10.00	m		
15	Supply & installation of 125A SFU cubical panel with HRC fuses in it near meter with all standardized components as usually required.	1.00	no		

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .					
Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
16	Supply & installation of 100A ICTPN switch with necessary M.S frame.	1.00	no		
17	Providing & laying 16 SWG metal conduits with its specials through floor and wall and through partition, counters in concealed form for data cables.				
	- 25 mm	20.00	m		
	- 20 mm	35.00	m		
18	Providing & laying of networking cable [D-Link make]				
	CAT - 6	400.00	rmt		
Total ELECTRICAL WORKS					
PART C DATA CABLE WORKS					
1	Providing and fixing 24-PORT SWITCH (LINKSYS-MAKE)	1.00	no.		
2	Providing and fixing JACK PANEL for 24 port switch D-link)	1.00	no.		
3	Providing and fixing of 12U RACK for above	1.00	no.		
4	Providing and fixing of CAT-6 patch cords with crimping at both ends (7 feet long-D-link)	16.00	no		
5	Providing and fixing of CAT-6 I/O outlets with with concealed box and dual face plates-D-LINK-make	14.00	no		
TOTAL DATA CABLE WORKS					
ABSTRACT :					

BOQ FOR INTERIOR FURNISHING WORKS FOR BANK OF INDIA -TIGAON (FARIDABAD)BRANCH .					
Sr. No	Description of Items	Qty	Unit	Rates in Fig.	Amount
a	Interior Works				
b	Electrical Works				
c	Data CableWorks -				
	TOTAL				