



Hazaribagh Zonal Office
Vidya Niwas
P.B. No.34
Zulu Park
Rajaram Mohan Roy Marg
Hazaribagh – 825 301
Jharkhand
Ph. 06546/222185, 227792,
226862
FAX06546/222900
E-Mail: Zohazaribagh@bankofindia.co.in

WEBSITE NOTIFICATION

**NOTICE CALLING FOR TENDERS FOR FURNISHING WORK OF OUR TOPA
BRANCH” AT ,+ POST- TOPA
DISTRICT- RAMGARH. (JHARKHAND)**

Bank of India, Hazaribagh Zonal Office invites quotation/rate/price/tender in sealed cover for Furnishing Work of our Topa Branch, District. Ramgarh, Jharkhand.

Approximate quantity of work involved in proposed Furnishing of “Bank Of India” Topa Branch District Ramgarh.(Jharkhand) is enclosed.

Persons/Firms interested in undertaking the work may apply with the following details:

- a)The person/firm should have minimum 3 years experience in Furnishing work/ interior decoration
- b)The person/firm should enclose documentary evidence in support of the experience.
- c)The Tender Form(Annexure-I) can be downloaded from Bank’s web site or can be obtained on payment Rs.250/=(non-refundable) by way of Demand Draft/Pay Order favouring Bank Of India from our office as mentioned above. If the application form is downloaded from website the applicant should submit Demand Draft/ Pay Order of Rs.250/= favouring Bank Of India along with the application, failing which their application is liable for rejection.
- d)Application for Furnishing work at Topa Branch ,District Ramgarh, should be submitted at Bank Of India, Zonal Office, Hazaribagh addressed to the Zonal Manager, Bank Of India, Hazaribagh Zone upto 5 p.m. on 21.11.2009.
- e)Sealed tender will be opened on 23.11.2009..at 1.00 p.m. in the Zonal Office, Hazaribagh by the tender opening committee. Applicants/contractors, who have submitted tenders, or their representatives, may attend the tender opening.
- f)Each tender should be accompanied by a Demand Draft for Rs.5000/= in favour of Bank of India, drawn on any scheduled bank in Hazaribagh. Demand Draft submitted by unsuccessful tenders will be returned, after opening of tenders. The Demand Draft submitted by the successful tender will be returned after successful completion of work.

Bank of India reserves the right to accept or reject any or all application/tender/quotation received without any reasons whatsoever.

**ZONAL MANAGER
HAZARIBAG ZONE**

**NOTICE FOR FURNISHING WORK OF OUR BANK OF INDIA TOPA BRANCH
AT & P.O.- TOPA
DISTRICT- RAMGARH ,(JHARKHAND)**

<u>Item No.</u>	<u>Brief Description of Item</u>	<u>Quantity</u>	<u>Rate in Rs.</u>	<u>Amount</u>
1.	<u>FRONT OFFICE COUNTER</u>		Rft.8.00	
	<p>Providing & Fixing in position from office counter 2'6 " wide as per Drawing no. (1A,1B,1C,1D &15) compromising of following complete in all respects:</p> <p>i)Working Top made with 25 mm thick plywood finished with 1mm thick laminate outside edge of the working top shall be provided with 1/1/4" x 1" Teack wood moulding finished with melamine polish .Inside edge will be provided 1/2"x1"T.W beading patti with melamine finish.</p> <p>ii)Vertical facia (Apron) made with 18 mm thick plywood finished with 1 mm thick laminate with 1 mm thick groove at the joint of laminate of two different shades.</p> <p>iii)Vertical Drop(Horizontal band) shall be provided on the facia below the working top made with 18 mm thick plywood finished with 1 mm thick laminate with provision for concealed light 1 mm thick groove shall be provided at the joint of two different shades of laminate.</p> <p>iv)Glazed partition above working top to be provided with 12 mm. Thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S.S finished D brackets as shown in drawing the exposed edges of the glass shall be finished in the mirror polish.</p> <p>v)3' 10" high Boxing(10' x 10") made with 18 mm thick plywood finished with 1 mm thick laminate including providing and fixing 6 mm thick square frosted glass at a height 3' 2" above finished in floor level.</p> <p>vi)1' 9" height Boxing(5" x 5") made with 12 mm. thick plywood finished with 1.mm thick laminate.</p> <p>vii)Vertical supports made with 18 mm thick plywood finished with white enamel paint</p> <p>viii)Telescopic CPU Stand/readymade keyboard tray shall be provided of approved model and make.</p> <p>ix)Footrest made with T.W. member of size 4"x1.5" finished with French polish.</p> <p>x)Drawer units as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1.mm. thick laminate &all other sides shall be finished with White enamel paint. The drawer will be provided with Handles (stainless steel finish) & channels as per approval of the project consultant/Bank.</p>			

xi)Boxing as per drawing made with 12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for electrical conduiting &at the bottom for the LAN cable/telephone wire conduiting. The item to include all necessary hardware and fittings in stainless steel finish Lipping to all edges & making provision only for electrical fittings behind the front vertical drop &also in the10"x10" Boxing as shown in the drawing .Necessary beading with melamine polish for fixing the glass are to be provided.

2.CASH COUNTER:

Rft.10.0

Providing & Fixing in position Cash counter 2' 9" wide as per Drawing no.(2A, 2B, 2C, 2D, 2E & 2F) comprising of following:

- i)Working Top table with 25 mm thick ply wood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1.25"x1" teak wood beading patti with melamine polish.
- ii)Vertical facial(Apron) made with 18mm thick plywood finished with 1mm thick laminate groove at the joint of laminates of two different shades.
- iii)Vertical Drop(Horizontal Band) shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light 1"thick groove shall be provided at the joint of two different shades of laminate.
- iv)Glazed partition 1' 4" height above working top provided with 12mm,thick toughened and frosted glass besides non-transparent film from inside fixed to partition as per fixing details and to boxing with concealed S.S finished with D brackets as shown in the drawing. The exposed of the glass shall be finished in mirror polish.
- v)Transaction Top shall be provided with 12mm thick tough finished glass(partly glazed partly frosted) fixed horizontally with concealed stainless steel D bracket. Both exposed edges(inside &outside)shall be moulded &finished in mirror polish.
- vi)Glazed partition having height 1'0" above the transaction top(in facia) shall be provided with 12mm thick clear glass with cut out of 8"x4"as per drawing The edge of cut out and the top edge of glass are to fixed to partition as per fixing details and to boxing with concealed S. S. finished D brackets as shown in clear glass above the sitt to be fixed as per fixing details & to boxing with concealed S .S finished D brackets as shown in the drawing. The exposed edges shall be finished in mirror polish.
- vii)7' 7" height Boxing(10' x 10") made with 18mm thick plywood as per drawing with 1'6' horizontal extension at the top including provision & fixing 6mm thick square frosted glass at the ht of 5'11" above finished floor level.
- viii)1' 9" height Boxing(5" x 5") made with 12mm plywood finished with 1mm thick laminate are to be provided.
- ix)Telescopic CPU stand/ ready made keyboard tray shall be provided of approved model & make.
- x)Footrest made with teak wood member of size 4"x1.5" finished with French polish.
- xi)The drawer unit as per drawing shall be provided & each drawer should have vertical partitions for keeping the currency notes & multipurpose Godrej locks Facia of drawer unit shall be finished with 1mm thick laminate & all other sides shall be finished with white enamel paint.

The drawers will be provided with handles (stainless steel Finish) and channels as per approved of the project Engineer /Bank.

xii)Boxing as per drawing made with 12mm thick plywood finished with synthetic enamel paint shall be provided below the table top for the LAN cabling/ Telephone wire conduiting. The item to include all necessary hardware & fittings In stainless steel finish ,ipping to all edges & making Provision only for electrical fitting behind the vertical Drop & also in the 10"x10" boxing as shown in the Drawing, Necessary beading with matching melamine Polish for fixing the glass are to be provided as per Drawing/ as directed.

3 Parly Glzed partition For cash cabins

Sft.247.00

Providing and fixing in position 7' 7" high partly glazed partition for cash cabins As per drawing Nos. (2A, 2B, 2C, 2D & 2E) including door drawing No. (12) In framework at 2' x 2' grid (horizontally and vertically) comprising of 2" x 1.1/2 T.W Section and /or as per frame work shown in the drawing with 6 mm plywood on both Sides finished with 1 mm thick laminates of approved shade and colour as shown in Drawing Item to include 8 mm thick glass with etching and frosting as per design and 2"x2' T.W. member for door sides and glass and T.W. door frame to take 8mm thick glass with etching and frosting. The door will be Provided with T.W. louvers finished in melamine polish of matching laminate colour. The doors are also to be provided with Ggodrej Night Latch. Two wooden trays are also to be provided in the glass and the edges of the glass cutouts are to be finished in mirror polish. All exposed T.W. surface to be finished in melamine polish of Matching laminate colour as directed including all necessary stainless steel finish Fitting / hardware door closers Godrej locks and wood preservative paint etc. as per List if approved by the project consultant / bank complete in all respects.

4..Providing and fixing of alumunium jail of approved quality and Make with proper beats including cost of all hardware fittings as Required for the job on the top of cash cabins and counting area. Sft:70.00

5.Providing and fixing of wall paneling on the columns up to 7" in height with 6mm plywood with 1mm thick laminate finished It has to match with the partition. The plywood is to be fixed over 2"x2" T.W, vertically on the pillars at required spacing as per Project engineer/Bank. Sft30.

7.Notice Board. As per specification of Bank. Sft 12.

8.Voucher/cash box :1Nos.